

CORRIGENDUM-1

Dt: 23.08.2019

Tender No: WAP/ENVT/ CSEZ/H-3082/2019/16 dated 05.08.2019

Name of the work: Construction of SDF Building in CSEZ - Supply, installation, testing and commissioning of Substation (2x1250 KVA), DG Sets (2x500 KVA), Connected HT & LT works, Street Lights etc

Reply to Pre Bid Queries

1. BOQ Item no.2 RMU is four way with 3 nos. LBS and 1 no. VCB
2. BOQ Item no.3 (a) HT Metering mentioned in the unitized substation is multi-function meter having indications including voltage on HT side.
3. BOQ Item no 9 Oil tank capacity of the DG set is as per manufacture design, however fuel indication should be in liters. The Governor of the Diesel engine should be electronic type The testing has to be done for continuously 8 hours with 10% overload for 1 hour. Make of the alternator shall be Stamford, Leroysoner, Mechalte.
4. The inspection of DG set need to be arranged as per the details given below;
 - a. Cumins: company works or Powerica (OEM)
 - b. Volvo and Parkinsons: company works or supernova (OEM).
 - c. Caterpillar: Company works or anyone of the OEM in South India.
5. BOQ Item no 14, APFC panel, sub item (g) thyristor is not required.
6. BOQ Item no 26 XLPE copper cable make can be same make of XLPE aluminium cable.
7. Sand filter and carbon filter shall be with MS tank only.
8. Model of K Light fitting is PRINCE ORNA MINI.
9. Audit report of 3 years shall be from 2015-16 onwards.

**Sd/-
General Manager (SEZ)**